Manhole Inspection Report



Date:

Customer:

05/15/2018

Weather:

Coding: **RZMACP**

MH#:

M-804-029

Owner: NA Len. Surveyed: 13.1

P.O.#:

Surveyor: Cert. #:

Rim to Invert: Jen Costello

> Concrete Wall Material:

14.7

(reinforced)

Street:

Intersection of Hickey St. and Lawre Project:

Hobart, IN

City:

GPS Northing:

U-907-5518

2909399.889

Location:

GPS Easting:

2909399.889

Drain Area:

Northeast

GPS Accuracy: **Sub-Meter**

Cover Shape:

Circular

Hobart, IN

Evidence of Surcharge:

No

Cover Size: Comments: 22.5

Potential for Runoff:

None

O&M Index:

0.00 5.00

O&M Quick: Structural Quick: 0000 5100

5100

O&M Rating: Structural Rating:

Overall Rating:

0.00 5.00 5.00

Structural Index: Overall Index:

5.00 Overall Quick:

	Code	Observation	Video (sec)	Grade
804-029				
.0	MGP	General Photo	10	NA
1.6	MGO	General Observation	27	NA
2.6	HSV	Hole Soil Visible	42	S 5
/13.1	MGO	General Observation	75	NA



Description:	General Photo
Distance (ft):	.0
Structural Grade:	0
O&M Grade:	0
Clock Start/From:	
Clock To:	
1st Value:	
2nd Value:	
Value Percent:	
Step:	NO
Remarks:	ACCESS MH

MGP

Wednesday, May 3, 2023

Code:



Code: MGO

Description: General Observation

Distance (ft): 1.6
Structural Grade: 0
O&M Grade: 0

Clock Start/From:

Clock To: 1st Value: 2nd Value: Value Percent:

Step: NO

Remarks: UNDERSIDE OF FRAME



Code: HSV

Description: Hole Soil Visible

Distance (ft): 2.6
Structural Grade: 5

O&M Grade: 0

Clock Start/From: 9

Clock To:

1st Value: 2nd Value: Value Percent:

Step: NO

Remarks:



Code: MGO

Description: General Observation

Distance (ft): 13.1
Structural Grade: 0

O&M Grade: 0

Clock Start/From:

Clock Start/Fro Clock To: 1st Value: 2nd Value: Value Percent:

Step: NO

Remarks: END SURVEY

Wednesday, May 3, 2023 3