


Profile/Photo Observation Report



Date:	04/26/2018	Weather:		Coding:	PACP 6.0
Pipe Length (ft):		Owner:	City of Hobart	Pre Clean:	No Pre-Cleaning
P.O.#:	101	Surveyor:	M. Pielacha	PSR:	P-505-006-005
Customer:	City of Hobart	Clean Date:		Shape:	C

Street:	California Street	Flow Control:	Not Controlled
City:	Hobart, IN	Year Renewed:	
Location:	Light Highway	Tape/Media #:	DEP 101
Purpose:	Routine Assessment	Dia/Height:	15"
Use:	Sanitary	Material:	VCP
Drain Area:		Lining:	
Category:	NA		
Comment:	YES501824 Submittal 2		
Location Details:		Direction of Survey:	Upstream
US MH:	M-505-006	DS MH:	M-505-005
		Total Length Surveyed (ft):	91.1

O&M Index:	2.92	O&M Quick:	3A21	O&M Rating:	35.00
Structural Index:	0.00	Structural Quick:	0000	Structural Rating:	0.00
Overall Index:	2.92	Overall Quick:	3A21	Overall Rating:	35.00

	Position	Code	Observation	Video (sec)	Grade
		M-505-005			
	.0	AMH	Manhole	0	NA
	.0	MWL	Water Level	13	NA
	5.0	TF	Tap Factory	28	NA
	14.3	DSF(S01)	Deposits Settled Fine	83	M 3
	25.5	TB	Tap Break-in	309	NA
	32.1	TFC	Tap Factory Capped	546	NA
	62.6	TBI	Tap Break-in Intruding	614	M 2
	64.8	DSF(F01)	Deposits Settled Fine	652	M 3
	89.9	OBR	Obstacle Rocks	695	M 3
	91.1	AMH	Manhole	706	NA
		M-505-006			



Code: **AMH**
 Description: **Manhole**

 Distance (ft): **.0**
 Structural Grade: **0**
 O&M Grade: **0**
 Clock Start/From:
 Clock To:
 1st Value:
 2nd Value:
 Value Percent:
 Continuous Index:
 Within 8" of Joint: **NO**
 Remarks: **M-505-005**



Code:	MWL
Description:	Water Level
Distance (ft):	.0
Structural Grade:	0
O&M Grade:	0
Clock Start/From:	
Clock To:	
1st Value:	
2nd Value:	
Value Percent:	10.000
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	



Code:	TF
Description:	Tap Factory
Distance (ft):	5.0
Structural Grade:	0
O&M Grade:	0
Clock Start/From:	9
Clock To:	
1st Value:	4.000
2nd Value:	
Value Percent:	
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	



Code:	DSF
Description:	Deposits Settled Fine
Distance (ft):	14.3
Structural Grade:	0
O&M Grade:	3
Clock Start/From:	4
Clock To:	8
1st Value:	
2nd Value:	
Value Percent:	20.000
Continuous Index:	S01
Within 8" of Joint:	YES
Remarks:	



Code:	TB
Description:	Tap Break-in
Distance (ft):	25.5
Structural Grade:	0
O&M Grade:	0
Clock Start/From:	2
Clock To:	
1st Value:	4.000
2nd Value:	
Value Percent:	
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	



Code:	TFC
Description:	Tap Factory Capped
Distance (ft):	32.1
Structural Grade:	0
O&M Grade:	0
Clock Start/From:	2
Clock To:	
1st Value:	4.000
2nd Value:	
Value Percent:	
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	



Code:	TBI
Description:	Tap Break-in Intruding
Distance (ft):	62.6
Structural Grade:	0
O&M Grade:	2
Clock Start/From:	9
Clock To:	
1st Value:	4.000
2nd Value:	3.000
Value Percent:	
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	



Code:	DSF
Description:	Deposits Settled Fine
Distance (ft):	64.8
Structural Grade:	0
O&M Grade:	3
Clock Start/From:	4
Clock To:	8
1st Value:	
2nd Value:	
Value Percent:	20.000
Continuous Index:	F01
Within 8" of Joint:	NO
Remarks:	



Code:	OBR
Description:	Obstacle Rocks
Distance (ft):	89.9
Structural Grade:	0
O&M Grade:	3
Clock Start/From:	6
Clock To:	
1st Value:	
2nd Value:	
Value Percent:	15.000
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	



Code:	AMH
Description:	Manhole
Distance (ft):	91.1
Structural Grade:	0
O&M Grade:	0
Clock Start/From:	
Clock To:	
1st Value:	
2nd Value:	
Value Percent:	
Continuous Index:	
Within 8" of Joint:	NO
Remarks:	M-505-006